

**CORRIGENDUM-I**

Name of work : Construction of a New Academic Building at Calicut International Airport  
 Tendered Amount : ₹1,17,00,981/- (Excluding GST)

The below mentioned amendments is made to the BOQ in Tender Document Published on 18.07.2025

Sl No	Item No.	Description	Unit As published in NIT	Unit To be read as
24	21.1.1.2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer in charge. (Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	Sqm	Kg

All other terms and conditions remain unchanged. This shall form part of tender document.

-Sd-

Engg Wing  
 Airport School Management Committee